TOC – Critical chain

J.Skorkovský

ESF-MU, KPH

TOC concisely I (see PWP presentation about TOC)

A modest repetition of TOC, because the theory of the critical chain
is built on this theory

- origin: Eliahu Moshe Goldratt, Jerusalem

- cost world<->throughput world

- analogy weight of the chain – solidity of the chain

- how to find a bottleneck?

- tools of TOC – tree structures

- Five TOC steps

- CRT – EC – TT – PT – FRT meaning:

- Current Reality Tree - Evaporating Cloud Tree– Transition Tree -
  - Prerequisite Tree – Future Reality Tree

TOC concisely I (see PWP presentation about TOC)

- **bottleneck** in the project management is a critical path

- finding (assessment) of bottleneck is not easy and often it is not explicit (uncompromising)

- everybody knows something about TOC and nobody knows **how to implement it** to the real world- and this is again another bottleneck (tendon of Achilles from the heel to the scruff)

TOC-five steps (revision)

Five steps process:

Step 0.   Identify the Goal of the System/Organization
Step 0.5 Establish a way to measure progress to Goal

- **Step 1. *Identify*** the system's constraint.

- **Step 2. *Exploit*** the system's constraint**.**

- **Step 3. *Subordinate*** everything else to the above decision.

- **Step 4. *Elevate*** the system's constraint**.**

- **Step 5.** If a constraint is broken (that is, relieved or improved), go back to Step 1. But don't allow ***inertia*** to become a constraint**.**

Linear image of the project

- activities – abscissas – Gantt graph
- constantly changing conditions (Parkinson low, Murphy low, Student syndrome, customer changes - „fancies ","caprices".. ….)

Trouble

Trouble

Parkinson s law

- **Parkinson's Law** is the old adage that work expands to fill the time allotted. Put simply, the amount of work required adjusts (usually increasing) to the time available for its completion. The term was first coined by Cyril Northcote **Parkinson**

Parkinson s laws

- Work complicates to fill the available time
- The demand upon a resource tends to expand to match the supply of the resource (If the price is zero). The reverse is not true.

Parkinson's Law

More Time = Less Effort Needed
Less Time = More Effort Needed

Effort

Time Allocated

Parallel image of the project

PlannerOne Scheduler

PlannerOne Resource Planner

Project and its budget

- price of the whole project (see MS Dynamics NAV next slide)

- project length (time)

- project stages and length of each activity

- assigned resources to every activity and their capacities (time per defined period)

- time reserves (buffers-time reserves) and their estimation

- unfavourable influences (see Murphy s lows - http://murphy.euweb.cz, etc.)

- additional activities (unexpected costs)

Projects and MS Dynamics NAV

Projects and MS Dynamics NAV

Job Task No.	Description	Job Task Type	Totaling	Job Posting Group	WIP-Total	WIP Method	Start Date	End Date	Schedule (Total Cost)
				Filter: DEERFIELD, 8 WP					
1000	**Setting up Eight Work Areas**	Begin-Total							
1100	**Preliminary Services**	Begin-Total							
1110	Determining Specifications	Posting		SETTING UP			13.1.2019	13.1.2019	107,80
1120	Selecting Furnishings	Posting		SETTING UP			14.1.2019	14.1.2019	107,80
1130	Obtaining Customer Approval	Posting		SETTING UP			17.1.2019	17.1.2019	107,80
1190	**Total Preliminary Services**	End-Total	1100..1190						323,40
1200	**Assembling the Furniture etc.**	Begin-Total							
1210	Assembling the Furniture etc.	Posting		SETTING UP			23.1.2019	23.1.2019	11 000,10
1290	**Total Assembling the Furniture**	End-Total	1200..1290						11 000,10
1300	**Closing the Job**	Begin-Total							
1310	Meeting with the Customer	Posting		SETTING UP			27.1.2019	31.1.2019	107,80
1390	**Total Closing the Job**	End-Total	1300..1390						107,80
9990	**Total Setting up Eight Work Areas**	End-Total	1000..9990						11 431,30

List o tasks and related costs (scheduled and used)

Schedule : The planning line contains expected usage for the job that will not be invoiced to the customer. You use this option if the costumer will be invoiced from a different planning line (of type Contract or Both Schedule or Contract), or if the expected usage for this planning line is not chargeable.

Contract : The planning line specifies an amount that should be invoiced to the customer, but no usage relates to the line. You use this option if no schedule of usage has been planned for the job, or if the expected usage for the job has been specified on different planning lines (of type Schedule).

Line Type	Planning Date	Document No.	Job No.	Job Task No.	Type	No.	Description	Unit of Measure Code	Quantity	Unit Cost	Unit Cost (LCY)	Unit Price	Total Cost
Schedule	25.01.12		DEERFIELD, …	1210	Resource	MARK	Delivering and Assembling	HOUR	20	31,90	31,90	54,00	638,00
Contract	25.01.12		DEERFIELD, …	1210	Resource	MARK	Delivering and Assembling	HOUR	20	31,90	31,90	54,00	638,00

Projects and MS Dynamics NAV

General	Invoicing	Personal Data

No. . . . . **MARK** ✎   Search Name . . . . . . MARK HANSON

Name . . . . Mark Hanson   Resource Group No. . . .

Type . . . . Person ▾   Blocked . . . . ☐

Base Unit of Measure . . HOUR ⬆   Last Date Modified . . . 25.01.12

Resource and assigned capacitiy

No.	Name	02.10.15	03.10.15	04.10.15	05.10.15	06.10.15	07.10.15	08.10.15	09.10.15	10
LIFT	Lift for Furniture	0	0	0	0	0	0	0	0	
LINDA	Linda Martin	0	0	0	0	0	0	0	0	
MARK	Mark Hanson	4	0	0	8	8	8	8	4	
MARY	Mary A. Dempsey	0	0	0	0	0	0	0	0	
TIMOTHY	Timothy Sneath	0	0	0	0	0	0	0	0	

Selected Murphy s laws

- If your attack is going well, you have walked into an ambush (trap)
- Planner is alerted about modification of the plan exactly in the moment, when the plan is finally adjusted
- To carry out $n+1$ trivialities you need two times more time than time necessary to carry out n trivialities (law 99 %)
- **If anything can go wrong, it will**
- Any given program, when running, is obsolete
- No matter how many resources you have, it is never enough

Resources and orders

Matrix structure of multi-project environment – responsibility
of project managers and responsibility of department managers are **in conflict**

Project manager 1
(manages O2

Project manager 2
(manages O1)

Chief 1

Chief 2

overload

capacity

Order 2 =O2

Resource E

Resource

Order 1=O1

time

Partial time of any activity in the project

Variability of the real time assigned to activity

Probability– median an element of statistical file,
which is after sorting in the middle .Median of the set (1,5,2,2,1) is 2

100 „5-miniutes meeting happened.
How many times it took 5 minutes only ?

Colleague ask for a quick rendez-vous: „Do not worry, it will take maximum 5 minutes!".
How long it takes on average?

Project environment is very complicated because of integration linkages and their dependencies

A -2

B -5

+10

C -1

F 3%

D -7

E +10

Probability of finishing tasks A to E in time is 50%. (50*50*….*50=3,125 %)

What is a probability, that task F will start in time ?

How the timely finishing of the tasks A,B,C and D will influence the integration point ?

a) saving are fully wasted

b) delay in one task will be immediately transferred to the next project task (activity) see **+10**

Project environment is very complicated because of integration linkages and their dependencies

In order to start **B** in the upper branch, you have to finish **G** and also **B** in the lower branch. The probability, that **B** start in time is 50 % worse, than it was shown on the previous slide.

The project must be protected against influences of breakdowns (troubles)

Standard estimation with protecting buffers for every activity

| activity 1 | B | → | activity 2 | B | → | activity 3 | B |

B = buffer

| activity 1 | → | activity 2 | → | activity 3 | → | buffer |

1st step : every activity is shorten to 50 % of its original time size.
2nd step : **critical path buffer** at the end of the project
will have size of 50 % of the total sum of saved time
created by shortening all partial activities

Simplified scenario CPM and CCPM

| Task1 | → | Implicit Buffer 1 | → | Task 2 | → | Implicit Buffer 2 |

| Task1 | → | Task 2 | → | Explicit Buffer | → | Saved time |

Explicit-directly specified, opened
Implicit= hidden, internally defined, indirect

CPM = Critical Path Method

CCPM = Critical Chain Project Methodology

EC and project management

(EC=evaporating cloud)

Critical path, adjoining branches of the project and adjoining buffers (AB)

| activity 1 | activity 2 | activity 3 | Project buffer |

Critical path

| activity X | activity Y | AB |

Adjoining project branch

Buffer serves as a safety tool to accumulate reasons of **expected** and **unexpected** delays

Critical Path (CP)

• Critical path is defined as **the longest way** (meaning time) from the starting point of the project graph to the ending point.

• Every project has at least one critical path

The rules of Critical Path:

• Every delayed task on **CP** will essentially delay the whole project

• Truncation of duration of any task on CP will shorten whole project

Critical Path (CP)

- **Critical Path Method**, abbreviated **CPM**, or **Critical Path Analysis,** is a mathematically based algorithm for scheduling a set of project activities. It is an important tool for effective project management.

Critical Path (CP)

Project Network Diagram
- Any schematic display of the logical relat[...]
  of project activities.

Milestones

Activity

Critical Path (CP)

Building a CP diagram 1

Critical Path (CP)

Building a CP diagram 2

Critical Path (CP)

Building a CP diagram 3

Task ID	Duration	Dependency
A	7	
B	3	
C	6	A
D	3	B
E	3	D,F
F	2	B
G	3	C
H	2	E,G

Critical Path (CP)

Building a diagram 4 – calculating the **FORWARD PASS**

Early Starts and **Early Finishes** dates are calculated by means of **Forward Pass**

Critical Path (CP)

Building a diagram 5 – calculating the **BACKWARD PASS**

| 0 | I A | 7 |
| 0 | (7) | 7 |

| 7 | C | 13 |
| 7 | (6) | 13 |

| 13 | G | 16 |
| 13 | (3) | 16 |

S →

| 16 | H | 18 |
| 16 | (2) | 18 |

→ F

| 0 | B | 3 |
| 7 | (3) | 10 |

| 3 | D | 6 |
| 10 | (3) | 13 |

| 6 | E | 9 |
| 13 | (3) | 16 |

Planüberhang, Slip, Scivolo, Regresso, **Загрузочный периоды апраксия**

Slack

Slack

10-3=7

| 3 | F | 5 |
| 11 | (2) | 13 |

13-3=**10**

16-3=13

13-2=11

**Difference Forward-Backward :
you can start
7 minutes later and the time
of the project (duration)
is the same**

Late Starts and Late Finishes dates are calculated by means of Backward Pass

Critical Path (CP)

Building a diagram 6 − calculating the **FLOAT(SLACK)/CP**

Free Float (Slack): Amount of time a single task **can be delayed without** delaying the early start of any successor task =LS-ES or LF-EF

Slack=Float

Proper description (Home study) :Slack or **Float** provide flexibility in the project schedule. When leveraged properly, project managers can shift activities and resources to meet the project objectives and priorities. It is the amount of time an activity can be delayed without impacting other activities or the project end date and changes over the course of the project implementation.

Planner SW (calculated)
Earliest Start Date

Due Date

Today

Activity 1   Activity 2   Activity 3

Activity 1   Activity 2   Activity 3

Slack

Activity 1   Activity 2   Activity 3

Activity 1   Activity 2   Activity 3

Critical Path (CP)

CPM is helpful in :

- Project Planning and control.
- Time-cost trade-offs.
- Cost-benefit analysis.
- Reducing risk.

Critical Path (CP)

Limitation of CPM :

- Does not consider resource capacities.
- Less efficient use of buffer time.
- Less focus on non critical tasks that can cause risk.
- Based on only deterministic task duration.
- Critical Path can change during execution.

Multi-project Management

	w1	w2	w3	w4	w5	w6	w7	w8	w9	w10	w11	w12	w13	w14	DAP
Project 1	■			■	■			■	■			■			12
Project 2		■				■		■	■	■		■	■		12
Project 3			■			■	■			■	■			■	12

36

Bad multitasking causes, that one project will be significantly longer and no other project will be shorter

K1	K2	K3

	w1	w2	w3	w4	w5	w6	w7	w8	w9	w10	w11	w12		DAP
Project 1	■	■	■	■	■	■								6
Project 2			■	■	■	■	■	■						6
Project 3					■	■	■	■	■	■				6

18

Multitasking characterization

- people always **overestimate the length of their tasks**
- salesman offers impracticable terms (dates)
- The fight for reserves (capacities) causes, that all saved time is fully wasted (Student s syndrome)
- Reserves (if any) are used badly !!!!!!
- Bad use of reserves causes lack of transparent assignment
- Non transparent priorities are parents of bad multitasking
- Bad multitasking causes longer duration of all activities (tasks) and thus all the projects

CP definition (more in detail)

Critical path is defined as the longest way   (meaning time)
from the starting point of the project graph to the ending point

Critical path represents technological dependencies and given
times of every task on Critical path inclusive of necessary
condition for fulfilment of foregoing tasks (activities)
framed by integration points.

Critical Chain

Task

Resource and capacities

Contemplation I.

Computing power

Years

Result ->Stress

Contemplation II.

E-mails   Parallel telephoning   Parallel problem solving

a) Am I a multitasker ?

b) NO !! And my IQ went down 15 point due to parrel processing !

Contemplation III.

Is this the goal of my lifelong efforts?

Maybe not …. I guess
I reached another peak …

Critical chain definition

In TOC the Critical chain is defined as the longest way (meaning time) from the starting point of the project graph (Gantt) to the ending point which takes into account **technological dependencies** as well as time of the tasks and moreover, **capacities of assigned resources**.

With infinite capacities of resources you can consider Critical path=Critical chain

Multi-project management and critical resources (CCR) used in more that one project branch

Project buffer

Disadvantageous variant

Critical chain

Critical path

CCR = Capacity Constrained Resource = X

Multi-project management and critical resources (CCR) used in more that one project branch

Project buffer

After transformation of activities

← Critical chain

Project management based on remainimg time in buffers – Buffer Management

- Buffers are used for timely warning and that is to say predicting and avoiding future problems related to project deadlines (milestones)

- It is also used as a guideline for corrective actions

Basic metrics showing the project status

- The partial size of Critical chain (CC) fulfilled in days (in %)
- How much of buffer size was used to fulfil above mentioned partial size of CC ?
- Trend of project (buffer consumption graph- see next slide)
- Consumption of the financial buffer
- Priorities – bigger buffer penetration- bigger priority
- Adjoining branches have always lower priorities
- It is not allowed to create bad multitasking

Trends of the project

Trend of the project advancement – (another angle of view)

100 %

Buffer Penetration

Action

Action plan

OK

0 %

100 % *Time remaining till the end of the project* 0 %

Planning - principles

We are working with plan , which takes into account different times of tasks :

- start of the tasks are changed based on termination of preceding tasks

- you have to react in project in such a way , that handover is done as a baton pass during races

Today

| A1 | C1 | D1 | Buffer |

B1 B

Planned start   2   4   6   8   10   12

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

100%

Buffer penetration
4 days

0

100%

Critical chain completion
8 days

Planning - principles

A1 did not started yet , because this A1 resource is still working on another order (task), which may be part of another project

B1 already started an for completion will need another two days

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Plan 2nd day after start

A1 started and will be finished (completed) tomorrow.

B1 will be finished (completed) tomorrow

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Plan 3rd day after start

A1 despite all efforts resource A1 needs another day to complete.

B1 has completed his work with 2 days delay

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Resource MPM systems

Plan 6 day after start

A1 completed his task with 2 days delay

B1 completed his task with 2 days delay

C1 completed his task 1 day earlier than expected (planned)

D1 will start to work tomorrow

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Plan 8 day after start

A1 completed his task with 2 days delay

B1 completed his task with 2 days delay

C1 completed his task 1 day earlier than expected (planned)

D1 needs one day more to complete

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Plan 11 day after start

A1 completed his task with 2 days delay

B1 completed his task with 2 days delay

C1 completed his task 1 day earlier than expected (planned)

D1 completed his task with 2 days delay

Plan with sharp deadlines with buffers 50% (2+3+3=8 8+4=12)

Example of using real SW package to control project by CCPM methodology

https://www.youtube.com/watch?v=4ARI1qIG1vA

Clear way to setup and control priorities.

Setup of priorities of partial tasks based on assigned reserves.

Do as good as you can, but only where it is needed

reserves

Project Quick, resources A-E and activities X,Z,X,W, and V

Activity=Task

Resource and activity	Median of the required time
A-Y	**10 days**

You can say, that 50 % of any activities finish earlier, and other **50 %** will be delayed, meaning, that **10 days** represents **50 %** of the estimated time for chosen activity.

Project managers decided, that activity ends if **90 %** of estimated time will be consumed. It means, that they add a time buffer of **8 days** (for the safety reasons). 10 d= 50%, 20d=100%, 2d=10%, 20d-2d=18d, 18d-10d=**8days**

A-Y	B-Z	C-X	D-W	E-V

(90 %)

5 x 10 days=50 days

Time distribution

Frequency

10 days   18 days

Time

Five activities (tasks) and applied modifications

- If we consider for every activity time buffer 8 days we will get :

A-Y	B-Z	C-X	D-W	E-V

5 x 10 days= 50 days

A-Y	8	B-Z	8	C-X	8	D-W	8	E-V	8

5 x 18 days= 5 x (10+8)=90 days

Five activities and modifications (added buffers) and four types of troubles

| A-Y | 8 | B-Z | 8 | C-X | 8 | D-W | 8 | E-V | 8 |

| A-Y | | B-Z | C-X | | D-W | E-V |

Delayed „reporting"

Parkinson

We wait for resource D (even if C finished earlier)

Real delay

No one trouble causes project delay taking into consideration planned delivery date (agreed date of the project).
Dissipation of acquired time reserves was caused by company strategy saying strictly stick to the planned project schedule (example of rigid management)

Five projects after modification (buffers united to one and placed to the end of the project)

| A-Y | B-Z | C-X | D-W | E-V | 8 | 8 | 8 | 8 | 8 |

| A-Y | B-Z | C-X | D-W | E-V |

Parkinson

Little bit longer than 20 days median but shorter than 18 days

Earlier end of activity A

| 8 | 8 | 8 | 8 | 8 | = CPB=current project buffer = 40 days

| 8 | 8 | 4 | = new buffer = 50 % out of CPB, which makes CPB/2

Critical path- Critical chain

Critical path

START → Activity V (14 days, resource A) → Activity W (6 days, resource B) → Activity Z (4 days, resource D) → END

Activity X (6 days, resource C) → Activity Y (10 days, resource A)

Critical Chain

Project is considered as successful if is finished in expected time and financial budget is not exceeded

Critical chain with buffers

Length of the Critical Chain (white line):

7+5+2+7=21

and originally it was all in all 28 days

Activity V
7 days=14/2, **RES A**

Activity W
3=6/2 days, RES B

Adjoining buffer
1,5 days

START

Activity X
3=6/2 days, RES C

Activity Y
5=10/2 days, **RES A**

Activity Z
2=4/2 days, RES D

Project buffer
7 days

Adjoining buffer
1,5 days

$7=(7+5+2)/2$

END

Buffer consumption

| Activity A(10) | Activity B(10) | Project Buffer (10) |

10=(10+10)/2

| Activity A(5+8) | Activity B(10) | Project Buffer (10) |

Buffer penetration = 3 days

Rate of penetration is used to assign priorities to the partial activities

Priorities assigned to resources

- If one resource have (**red A**) to be assigned to two activities starting in the same moment so the first activity which will start is the one belonging to the project with bigger project buffer penetration.

- If none of all project buffers were penetrated with previous activities, so the first starts this activity which belongs to the critical chain.

A 1

Project Buffer 1

AB 1

Project Buffer 2

A 2

AB 2

AB-Adjoining Buffer

A2 starts firstly because PB 2 is partially consumed (penetrated)

Priorities assigned to resources

DFB 3   A 2   AB 2

Critical chain

A 1

Project Buffer 1

AB 1

Project Buffer 2

A 2   AB 3

This activity (**A1**) starts first because it is a part of the Critical chain and Project Buffer 1 is penetrated

Main benefits of the Critical Chain (CC) usage
(Home study)

- Every single project ends significantly earlier, than projects where other project management methods than CC were applied

- Total time needed to end more project than one is markedly shorter

- Promised delivery times are fulfilled with higher rate of credibility

- You will have more free capacity of all used resources

Main benefits of the Critical Chain (CC) usage

(Home study)

- Better initial estimation about project timing and thus bore accurate planning

- During starting of the projects you did not meet any problem taking into consideration drum resource

- Decrease of unfavourable effects such as Student syndrome, Murphy attacks and impacts of Parkinson s laws by redeployment and integration of all buffers to one and only one project buffer at the end of the project

- Utilization of benefits caused by earlier ended activities

- Use of reporting system which provides you with valuable information of buffer penetration , the extent of time reserves and thus better helping system for assigning priorities

Desirable attributes of a Project Manager

Different approaches to Project Management

Waterfall methodology–Big design up front, milestones,..no iterations !!
It is based on prediction

Agile methodology– Scrum (Sprints,..)- iterations approach

Critical Chain- based on TOC –
(see https://www.youtube.com/watch?v=mpc_FdAt75A)

Prince2 -Projects IN Controlled Environments (rolling wave planning)

Lean management

Waterfall - predictive approach

Clients may not know exactly what their requirements are before they see working software and so change their requirements, leading to redesign, redevelopment, and retesting, and increased costs

One of the differences between agile software development methods and waterfall is **the approach to quality and testing**. In the waterfall model, there is always a separate *testing phase* after a *build phase*; however, in **agile software development** (see next slide) testing is completed in the same iteration as programming

Agile PM approach – for instance SCRUM

Scrum is an iterative and incremental agile SW development framework for managing product development

A key principle of **Scrum** is the **dual recognition** that customers will change their minds about what they want or need (often called **requirements volatility**) and that there will be unpredictable challenges for which a **predictiv**e or planned approach is not suited

Sprint->Stage
Scrum ->Iteration, daily work

SCRUM

Prince2 (home study)

The seven Prince2 principles are:

1. Continued Business Justification
2. Learn from Experience
3. Defined Roles and Responsibilities
4. Manage by Stages
5. Manage by Exception
7. Focus on Products
8. Tailor to Suit the Project Environment

Not suitable for SW project e.g. SRUM,
based on best practice, use WBS,roles,… suitable for corporate projects,

Prince2 (home study)

Prince2 (home study)

**7 crucial themes, limitless benefits:**

Sets out the justification for each and every project, clearly highlighting what is required and, crucially, when.

Business Case

Project control mechanisms are clearly set out for key project personnel.

Progress

Organization

Project roles and responsibilities are clearly defined, for truly seamless project management.

Having a clear definition of a project's configuration management, issue management and change control are key to all you seek to achieve.

Change

PRINCE2®

Quality

A generic method based on proven principles, when you adopt PRINCE2, quality is assured.

Specialist aspects of the project can be easily integrated with the PRINCE2 method, for true success.

Planning

Risk

Risk analysis and management are key to any project's successful delivery.

Some slides to complete presentation – final review

Critical Chain Solutions

Drum prinicple- CCPM)

(CC=Critical chain)

Drum – system wide constraint, that sets the beat for the firm's **throughput**

Drum – person, department, policy, resource

Capacity Constraint Buffer (CCB) – safety margin between projects

Drum buffer – extra safety before the constraint (DB)

| | | | Project 1 buffer | CCB | | | | Project 2 buffer |

| | | | Project 1 buffer |

DB

Project management and Drum (Capacity Constraint resource) - principle of schedule projects based on drums

1. Identify the drum
2. Exploit the drum
   - Prepare a project schedule for ech project
   - Determine priority for the drum
   - Create the drum schedule
3. Subordinate the project schedules (next slide)
4. Elevate the capacity of the drum
5. Go back to step 2

Schedule project based on drum->Designate CC->
->Insert buffers capacity constraint buffers->Resolve conflicts ->Insert DB

Difference Between Buffer and Float (or Slack) - (home study)

People often get confused between buffer and float. They find these two terms similar; however, they are not.

The following are a few differences between the float and buffer:
•Float or slack is a critical path phenomenon, while buffer blongs to the critical chain.

•A float is a difference between the duration of the critical path and the non-critical path. A float is zero on a critical path.

•A buffer is based on contingencies (unpredictable actions). For example, the project buffer is about 50% of the safety time that you have removed from the activity estimate duration. Based on the definition of buffer, it is not zero on a critical chain or any other chain.

•A float is the same for all activities on a non-critical path, any activity can consume it partially or fully, and other activities can utilize balance. There is no further analysis.

•Any activity can also borrow a buffer if the activity is delayed. The project manager analyzes the remaining buffer to find the status of the project.

•Buffer can be divided into three categories: project buffer, feeding buffer and resource buffer

Complition of slides 16 and 17

Resource Dependencies Across Projects

Op = operation

Operations D and H are done by the same resource

Delays: If Op D on Project 1 is late, Op H on Project 2 also get delayed as its resource is blocked on Op D

Gains: Even if Op D finishes early, the resource cannot start Op H as has to wait for Op F finish

Resources

http://www.fortezzaconsulting.com/blog/5-myths/

https://www.workflowmax.com/blog/choose-your-project-management-methodology-pros-and-cons-of-agile-waterfall-prism-and-more

Very usefull one :
https://www.tutorialspoint.com/management_concepts/pareto_chart_tool.htm

Thanks for Your Attention